

CUNNANE STRATTON REYNOLDS
LAND PLANNING & DESIGN

THE RAILYARD, ALBERT QUAY, CORK.

Landscape Design Rationale

PROJECT NO. 23450

July 2024




| | |
|------------------------------------------------------|---------|
| Landscape Context | Page 3 |
| Green & Blue Infrastructure | Page 5 |
| Design Aims & Landscape Constraints | Page 7 |
| Design Concept: Inspiring Images-public Realm | Page 8 |
| Design Concept: Landscape Master Plan – Ground Plane | Page 9 |
| Design Concept: Ground Plane - Recreation & Amenity | Page 10 |
| Design Concept: Landscape Plans – Roof Terraces | Page 11 |
| Design Concept: Roof Terraces- Recreation & Amenity | Page 12 |
| Design Concept: Landscape Sections– Roof Terraces | Page 13 |
| Design Concept : Indicative Planting Imagery | Page 14 |
| Maintenance and Management | Page 17 |

LAND PLANNING & DESIGN

01. CONTEXT

LANDSCAPE CONTEXT



The proposal is for a Large-Scale Residential Development at the former Carey Tool Hire site, currently principally occupied by Park Facilities Management Ltd, Albert Quay, Cork City. The site is bounded by Albert Quay East to the north, Albert Street to the west, Albert Road to the south, and Navigation Square to the east. The proposed development site includes the former Blackrock and Passage Railway Terminus – Ticket Office, a Protected Structure, Ref. No. PS 1138, and which is also a Recorded Monument, CO074-119002, the two-storey former Cork, Blackrock and Passage Railway Offices, Protected Structure, Ref. No. PS 1137, and the Albert Road Post Box, which is also a Protected Structure Ref. No. PS942.

A developed network of footpaths in the immediate vicinity of the site provides excellent connectivity with the city centre and surrounding areas while dedicated bus and cycle lanes for Albert Quay are at an advanced stage of planning. The site faces onto the river lee and the boat marina at Custom House Quay. The closest green space, Shalom Park is situated to the south of the site within a five-minute walk of the proposed development. The park is popular with strollers and dog walkers and contains a playground and large areas of usable open space. Within a 2km walk is the popular Marina/Cork Harbour Green way and two large event venues, *Live at the Marquee* and *Supervalu Páirc Uí Chaoimh*.

Main Local Amenity & Recreation Links

-  Links to amenity green spaces/greenway
-  Links to amenity blueways

02. GREEN AND BLUE INFRASTRUCTURE PRINCIPLES

GREEN & BLUE INFRASTRUCTURE: PRINCIPLES AND THEMES

Green and Blue Infrastructure Strategy

The integration of amenity & recreation, circulation & connectivity, biodiversity, heritage elements and nature-based sustainable drainage.



- Heritage: Retain remnants of old railway tracks on site



- Biodiversity: Introduction of trees and shrubs on the brown-field site



- SuDS: Incorporation of nature-based solutions with rain gardens in soft landscape areas



- Amenity & Recreation: Incorporation of play and seating elements throughout the scheme together with circulation and permeability.



KEY COMPONENTS:

Open Spaces and Recreation: Provide well-connected green spaces and recreation areas that promote physical activity, interaction, and social well-being.

Vegetation and Biodiversity: Incorporate planting schemes and design features that promote biodiversity, provide habitats for wildlife, and improve people's health and well-being.

Sustainable Drainage Systems (SuDS): Use SuDS techniques to manage surface water runoff and mitigate flood risk and incorporate nature-based features where feasible.

Integration: SuDS can improve a development by creating habitats that encourage biodiversity and simultaneously enhance open space.



Rain gardens cultivated for pollinator species

PRINCIPLES:

Green & Blue Infrastructure strategies aim to create sustainable, resilient, and liveable communities that benefit both the environment and the people who inhabit them

KEY BENEFITS:

1. Nature rich beautiful places
2. Active and healthy places
3. Thriving and prospering
4. Improved water management
5. Resilient and climate positive places

LAND PLANNING & DESIGN

03. LANDSCAPE CONCEPT

DESIGN CONCEPT: DESIGN AIMS

Green & Blue Infrastructure: Settlement Level Network**Components:**

- The provision of safe and healthy recreational spaces throughout the site
- The planting of native/pollinator friendly trees and shrubs suitable for the long-term site objectives such as definition of space, screening, seasonality etc.
- The incorporation of nature-based solutions appropriate to the site ground conditions.
- GI management/maintenance operations



The landscape design strategy for Albert Quay focuses on:

- **Place Making:** the evolution of the site layout, reflects the site's historic land use and location on the South Docks, creating a sense of place/distinctiveness through the site.
- **Green & Blue Infrastructure:** provision of a framework across the site into which the proposed development will be integrated into.
- **Biodiversity** – Provision of greening measures to enhance the biodiversity potential of the site in line with the All-Ireland Pollinator Plan.
- **Destination Place:** providing an open and inviting outdoor destination that is uplifting and attractive for residents and visitors.
- **Accessibility:** Providing an accessible environment in line with principles of universal design.
- **Connectivity and Permeability:** allowing ease of movement through the development, legible routes and clear definition of space, in line with principles of DMURS.
- **Recreation and Amenity** - provision of safe, overlooked open spaces, routes and facilities through the site with access for all.
- **Community Building**– provision of multi-functional and flexible communal spaces within the development scheme through the inner courtyard and rooftop terraces.
- **Framing Views:** optimizing the experience of panoramic views.
- **Materiality:** careful selection of materials with regard to attractiveness, texture, robustness, durability, ease of maintenance and compatibility with local setting.
- The following **microclimatic factors** are for consideration in the development of landscape proposals for the ground plane courtyards and roof terraces:-
 - Sunlight availability
 - wind direction / thermal comfort
 - downdraft

The location of planters and seats on the roof terraces will be determined by the availability of sunlight and level of exposure to wind.

DESIGN CONCEPT: INSPIRING IMAGES - PUBLIC REALM (Indicative images)

Prioritisation of **'Place Making'** in the evolution of the site layout, through the delivery of sense of place/distinctiveness through the site with a nod to its railway heritage when it was an active hub, and rail tracks traversed the site.



DESIGN CONCEPT: LANDSCAPE MASTER PLAN – GROUND PLANE



Landscape Master Plan Ground Plan – Design Rationale

The design intent is for the inner courtyard to be a well-connected walking route, but also a destination, reminiscent of a city laneway removed from the busy trafficked streets that surround the site. People are invited in to meet, rest and enjoy their immediate surroundings in comfort in a lush green environment that stimulates the senses.

Design proposals include for:-

- a wide generously proportioned walking route kept open to allow pedestrian traffic to flow freely through the site while allowing space to sit, and to accommodate emergency and maintenance vehicles on occasion.
- The paving design is dynamic to reflect the movement of the spaces and the historic railway lines creating a sense of place, and is finely detailed and finished to a high standard,
- The route is framed with trees and shrubs in raised planters and/or rain gardens to engage the senses and enhance the biodiversity potential of the site, threaded with ample stopping spaces and seating,
- The building edges are alive with the activity of café and restaurants patrons, residents, and children at play, attracting people passing by in to engage

Note : see dwg. No. 23450-2-101
Landscape Masterplan for more detail

DESIGN CONCEPT: GROUND PLANE - RECREATION & AMENITY (Indicative images)

Prioritising providing an interactive environment that provides for a strong communal hub for gathering, socialising, seating, play stopping and meeting places blended living environment/hub with active edges that enliven this urban space




DESIGN CONCEPT: LANDSCAPE PLANS – ROOF TERRACES

Terrace Landscape Design Rationale

The roof gardens have been designed to cater for the outdoor recreational and amenity needs of future apartment dwellers, young and old. Thermal comfort can be a concern on roof terraces but to provide multifunctional amenity spaces, a mix of open and sheltered areas are proposed for active and passive pursuits.

The micro-climate factors which can impact on the enjoyment of outdoor roof garden/terrace spaces on the upper levels of tall buildings will be mitigated/addressed in the following ways:-

- a 1.6m high glazed guardrail around the perimeter of each terrace will provide a measure of protection from gusts and squalls for terrace users, both seated and standing,
- seating will be provided at different locations within each terrace space to afford users the opportunity of finding comfortable places in which to sit and take shelter from prevailing wind/downdrafts on any given day,
- planters with small multi-stem trees, shrubs and ornamental herbaceous perennials will be sited next to all seating areas to help filter wind and create a more thermally comfortable outdoor environment,
- planting will be augmented where appropriate to help filter wind from the southwest and at building entrances where this will help to mitigate the effects of downdraft.





9th Floor Terrace Plan





12th Floor Terrace Plan

DESIGN CONCEPT: ROOF TERRACES- RECREATION & AMENITY (Indicative images)



Prioritising providing a flexible liveable communal spaces that benefit both the environment and the people who inhabit them, separated from the busy city streets below.



DESIGN CONCEPT: LANDSCAPE SECTIONS- ROOF TERRACES



Multifunctional communal amenity spaces with lush and textured planting.




B - 9th Floor Terrace Section



(Indicative images)


DESIGN CONCEPT : COURTYARD & BUILDING EDGE PLANTING IMAGERY

Maximizing the diversity of native and pollinator plants within a given area is key to providing adequate resources to support a range of pollinator species.



DESIGN CONCEPT : COURTYARD & PUBLIC REALM TREE IMAGERY

(Indicative images)



LAND PLANNING & DESIGN

04. MAINTENANCE & MANAGEMENT

INTRODUCTION

This document sets out the proposed maintenance and management plans for the establishment and ongoing maintenance of the landscape element of the proposed development. There will be a minimum 18 months defects period on all soft landscape works implemented. Thereafter the landscaping will be maintained in perpetuity consecutive 12 months periods.

1.0 SOFT LANDSCAPE WORKS SPECIFICATIONS

1.1 Site Clearance Generally

- General: Remove rubbish, concrete, metal, glass, decayed vegetation and contaminated topsoil.
- Stones: Remove those with any dimension exceeding 25mm.
- Contamination: Remove material containing toxins, pathogens or other extraneous substances harmful to plant, animal or human life. In accordance with current Health and safety legislation.
- Vegetation: remove all weed growth.
- Large roots: Grub up and dispose of without undue disturbance of soil and adjacent areas.

1.2 Weed Control

Remove all noxious and undesirable weeds from the sit. Weeds shall include: Ragwort, Himalayan Balsam, Giant hogweed & Japanese knotweed, Thistle, Dock, Common Barberry, Male Wild Hop and Spring Wild Oat, or any other noxious species identified by the Department of Environment. For the removal of certain species such as Japanese Knotweed a method statement is to be prepared and submitted to the Department of Environment.

1.3 Standards

In preparing the landscaping, supplying plants and maintaining the landscaping the following standards are to be adhere to:

| | |
|-------------------|---------------------------------------------------------------------------------------------------------------------|
| • BS 3882 | Specification for topsoil and requirements for use |
| • BS 3936-1 to 10 | Specification for the supply of nursery stock |
| • NPS | National Plant Specification |
| • BS 3998 | Tree Works: Recommendations |
| • BS 4428 | Code of Practice for general Landscape Operations |
| • BS 5837 | Tree in relation to Construction |
| • BS 7370-1 to 5 | Grounds Maintenance |
| • BS 8545 | Trees: from nursery to independence in the landscape-recommendations |
| • BS 8601 | Specification for subsoil and required use |
| • BS EN 1722-9 | Fences Specification for mild steel - low carbon steel - fences with round or square verticals and flat horizontals |

The latest publications for each document are to be used.

1.4 Soil Conditions

- Soil for cultivating and planting: Moist, friable and do not plant if waterlogged.
- Frozen or snow covered soil: Give notice before planting. Provide additional root protection. Prevent planting pit sides and bases and backfill materials from freezing.

1.5 Climatic Conditions

- General: Carry out the work while soil and weather conditions are suitable.
- Strong winds: Do not plant.

1.6 Times of year for planting

- Deciduous trees and shrubs: Late October to early March.
- Evergreens/Conifers: October/November or Feb/ March.
- Container Grown plants: Any time of years.

1.7 Mechanical Tools

Restrictions: Do not use within 100mm of tree and plant stems.

1.8 Watering

- Quantity: Wet full depth of topsoil.
- Application: Even and without damaging or displacing plants or soil.
- Frequency: As necessary to ensure establishment and continued thriving of planting.

1.9 Preparation, Planting and Mulching Materials

General: Free from toxins, pathogens or other extraneous substances harmful to plant, animal or human life.

1.10 Plants/ Trees - General

- Condition: Materially undamaged, sturdy, healthy and vigorous.
- Appearance: Of good shape and without elongated shoots.
- Hardiness: Grown in a suitable environment and hardened off.
- Health: Free from pests, diseases, discolouration, weeds and physiological disorders.
- Budded or grafted plants: Bottom worked.
- Root system and condition: Balanced with branch system.
- Species: True to name.

1.11 Container Grown Plants/ Trees

- Growing medium: With adequate nutrients for plants to thrive until permanently planted.
- Plants: Centred in containers, firmed and well watered.
- Root growth: Substantially filling containers, but not root bound, and in a condition conducive to successful transplanting.
- Hardiness: Grown in the open for at least two months before being supplied.
- Containers: With holes adequate for drainage when placed on any substrate commonly used under irrigation systems.

1.12 Labelling And Information

General: Provide each plant/ tree or group of plants/ trees of a single species or cultivar with supplier's labelling for delivery to site, showing:

- Full botanical name., Total number, Number of bundles, Part bundles.
- Supplier's name, Employer's name and project reference.
- Plant specification, in accordance with scheduled National Plant Specification categories and BS 3936.

1.13 Plant/ Tree Substitution

Plants/ trees unobtainable or known to be likely to be unobtainable at time of ordering. Submit alternatives, stating the price and difference from specified plants/ trees. Obtain approval before making any substitution.

1.14 Plant Handling, Storage Transport and Planting

- Standard: To HTA 'Handling and Establishing Landscape Plants'.
- Frost: Protect plants from frost.
- Handling: Handle plants with care. Protect from mechanical damage and do not subject to shock, e.g. by dropping from a vehicle.
- Planting: Upright or well balanced with best side to front.

1.15 Treatment of Tree Wounds

Cutting: Keep wounds as small as possible.

- Cut cleanly back to sound wood using sharp, clean tools.
- Leave branch collars. Do not cut flush with stem or trunk.
- Set cuts so that water will not collect on cut area.
- Fungicide/ Sealant: Do not apply unless instructed.

1.16 Protection of Existing Grass

- General: Protect areas affected by planting operations using boards/ tarpaulins.
- Excavated or imported material: Do not place directly on grass.

Duration: Minimum period.

1.17 Surplus Material

Subsoil, stones, debris, wrapping material, canes, ties, temporary labelling, rubbish, pruning's and other arising's: Remove.

1.18 General Planting/Seeding

- Planting shall be carried out within the contract period but not during periods of frost, drought, cold drying winds or when the soil is waterlogged, or when the moisture of the soil exceeds field capacity.
- All containers and protective coverings including biodegradable coverings to root systems shall be removed prior to planting. Roots, except for emergent vegetation, shall be teased out from the root-ball, spread evenly and not twisted.

All plant material shall be planted upright or placed so as to be well-balanced. Extreme care is to be taken to avoid damage to the root system, stem and branches when planting. The plant shall be positioned such that after planting the original soil mark on the stem is at finished ground level.

- Following completion of planting, grass seeding and turf laying, the soil over the whole of the planted, seeded or turfed area shall be sufficiently watered to achieve its field capacity.

- On completion of planting, watering and mulching, all areas shall be left tidy and weed-free and shall be maintained in a tidy and weed-free state until completion of the works.
- For shrub and transplant pit planting, notch planting and ordinary planting, the plant positions shall be set at equal centres in order to obtain a natural dense cover when mature. For notch and pit planting plants shall be planted in parallel lines. Planting positions in each row shall be staggered with the previous row.
- Finely-broken backfill material shall be carefully spread around roots and root trainers of all plants and the plants given slight shake to ensure that all interstices/ gaps are filled with soil, which shall then be consolidated by heeling. Careful filling and heeling shall continue as necessary at 150mm layers.

1.18.1 Mulching

Newly planted shrub areas shall be mulched immediately after planting to a depth of 50mm or in accordance with the details indicated on the drawing. Mulch shall be coarse chipped tree bark, composted for 2-4 months. Particle size 25-75mm diameter. No Fines.

1.18.2 After Planting & Mulching

- Watering: Immediately after planting, thoroughly and without damaging or displacing plants or soil.
- Firming: Lightly firm soil around plants and fork and/ or rake soil, without damaging roots, to a fine tilth with gentle cambers and no hollows.
- All areas shall be left tidy and weed-free and shall be maintained in a tidy and weed-free state until completion of the works.

1.19 Tree Planting

Attached in the appendix are typical tree planting details for this site.

1.19.1 Tree Pits

- Sizes: at least 300mm greater than rootball in all directions.
- Sloping ground: Maintain horizontal bases and vertical sides with no less than minimum depth throughout.
- Pit bottoms: With slightly raised centre. Break up to a depth of 100mm.
- Pit sides: Scarify.

1.19.2 Semi-Mature Trees

- Standard: Prepare roots and transplant to BS 8545.
- Planting shall be carried out by positioning the tree in the centre of the pit closely against the tree stake and spreading the tree roots to their fullest extent.
- Backfilling material: Previously prepared mixture of topsoil excavated from pit and additional compost as required.
- Immediately following planting, trees with stakes shall be secured with tree ties. Tree ties shall be fixed so that movement of the tree shall not cause damage or abrasion to the bark, top tie to be 50mm below top stake.

1.19.3 Staking Generally

Softwood, peeled chestnut, larch or pine, straight, free from projections and large or edge knots and with pointed lower end. Adjustable rubber ties to be fixed to all trees and at the correct size for the tree.

1.19.4 Mulch Circles/Squares

All existing trees/newly planted trees within open grass areas or grass verges shall have 50mm depth mulch circle/square of a maximum 1m diameter or as allowed by verge width.

1.20 Shrub Planting

- All shrubs are to be pit planted. General pit dimensions are to be wide enough to accommodate roots when fully spread and 75mm deeper than root system.
- Break up base of pit to a depth of 150 mm, incorporating soil ameliorant/ conditioner at 50 g/m².
- Pits to be backfilled with previously excavated material. Backfilling to be done in layers of 150mm depth; at each stage the filling to be firmly consolidated.
- Soil ameliorants can be premixed with the soil applied or mixed in during planting.
- Soil ameliorants to consist of an approved compost at 10L per m²; and 150g/m² of 10:10:10 NPK slow release fertilizer, or as approved.
- All shrub areas to be finished, with 75mm of medium grade bark mulch.

1.21 Hedgerow Planting

- Preparation: Dig trench to 500mm width for single staggered row, ensuing pit base is broken up 100mm deeper than plant rootball.
- Ameliorants: Compost at 10lt/m² and 10:10:10 NPK slow release fertiliser at 150g/m².
- Planting: Mix in soil ameliorants with excavated topsoil, or if there is poor topsoil then mix in with imported new topsoil. Firm down topsoil lightly in layers of 150mm by treading.
- Additional Requirements: If there is no existing fencing or barrier, install a protective fence to stop people walking through it until hedge is established. If there is livestock adjoining hedge install a stockproof fence or electrical fence 1m from hedge line until hedge is established.
- Prior to new growth cut the hedge back by 300mm to encourage new growth from base.

1.23 Removing Trees and Shrubs

- Identification: Clearly mark trees and hedges to be removed.
- Work near retained trees: Where canopies overlap, take down trees carefully in small sections to avoid damage to adjacent trees that are to be retained.

1.24 Failures of Planting

- Defects due to materials or workmanship not in accordance with the Contract: Plants/ trees/ shrubs that have failed to thrive.
 - Exclusions: Theft or malicious damage after completion.
 - Rectification: Replace with equivalent plants/ trees/ shrubs.
- Replacements: To match size of adjacent or nearby plants of same species or match original specification, whichever is the greater.

1.26 Grass Seeding**1.26.1 Herbicide Application**

- Type: Suitable for suppressing perennial weeds and existing grass.
- Glyphosate and other controlled chemical pesticides will not be used under any circumstances.
- Suitable herbicide use to the instruction of a registered professional user.
- Timing: Allow fallow period before cultivation.
- Duration: As manufacturer's recommendation.

1.26.2 Seedbed cleaning before sowing

Operations: Herbicides as per registered professional user only.

1.26.3 Cultivation

- Compacted topsoil: Break up to full depth.
- Soil ameliorant/ Conditioner/ Fertilizer are to be used to boost late seeding only. Type to be used is to be agreed with the administrating body depending on the time of year and the condition of the soil.
- Tilth: Reduce topsoil to a tilth suitable for blade grading.
 - Depth: 75 mm.
 - Particle size (maximum): 20 mm.
- Material brought to the surface: Remove stones and clay balls larger than 50 mm in any dimension, roots, tufts of grass, rubbish and debris.

1.26.4 Topsoiling

- Areas to be reinstated shall be top-soiled to a min. depth of 150mm.
- Quantity: Provide as necessary to make up any deficiency of topsoil existing on site and to complete the work.
- General: Do not use topsoil contaminated with subsoil, rubbish or other materials that are:
 - Corrosive, explosive or flammable;
 - Hazardous to human or animal life;
 - Detrimental to healthy plant growth.

1.26.5 Grading

- General appearance to be achieved: A fine graded finish to bring the ground to a uniform and even grade at the correct finished levels with smooth, flowing contours.
- Topsoil condition: Reasonably dry and workable.
- Contours: Smooth and flowing, with falls for adequate drainage.
- Hollows and ridges: Not permitted.
- Finished levels after settlement: 25 mm above adjoining paving, kerbs, manholes etc.
- Blade grading: May be used to adjust topsoil levels provided depth of topsoil is nowhere less than 150mm.
- Give notice: If required levels cannot be achieved by movement of existing soil.

1.26.6 Fertilizer for Seeded Areas

- Types: Apply both:
 - Superphosphate with a minimum of 18% water-soluble phosphoric acid.
 - A sulphate of ammonia with a minimum of 20% nitrogen.
- Application: Before final cultivation and three to five days before seeding/turfing.
- Coverage: Spread evenly, each type at 70 g/m², in transverse directions.

1.26.7 Final Cultivation

- Timing: After grading and fertilizing.
- Seed bed: Reduce to fine, firm tilth with good crumb structure.
- Depth: 50-100mm.
- Surface preparation: Rake to a true, even surface, friable and lightly firmed but not over compacted.
- Remove surface stones/earth clods exceeding:
 - Pastoral areas: 50mm.
 - Fine lawn areas: 10mm.
- Adjacent levels: Extend cultivation into existing adjacent grassed areas sufficient to ensure full marrying in of levels.

1.26.8 Grass Seed

- All seeds shall carry appropriate certificates.
- Seed shall be purchased fresh for each growing season and seed purchased impervious sowing seasons is not to be used.
- Seed shall be stored under non-transparent wrapping, off the ground, in a dry, shaded place, in well ventilated conditions under cover and shall be protected from vermin and contamination until required for use.
- No seeding shall take place until the seedbed is completed. All seeding shall be carried out within the sowing season.

1.26.9 Sowing

- General: Establish good seed contact with the root zone.
- Method: To suit soil type, proposed usage, location and weather conditions during and after sowing.
- Distribution: 2 equal sowings at right angles to each other.
- Protection: fence off areas with suitable fencing to stop people or animals from trampling new growth.

1.26.10 Grass sowing season

Grass seed generally: April to June or August to November.

1.27 Cleanliness

After completion of all works remove all debris and waste material from site.

- Soil and arisings: Remove from hard surfaces and grassed areas.
- General: Leave the works in a clean tidy condition at completion and after any maintenance operations.

2.0 MAINTENANCE

The maintenance programme will be organised on the basis of specific **performance standards** which must be met by the contractor at all times and will be the basis on which this contract will be assessed. Along with these performance standards a monthly report sheet shall be filled out and returned each month. Details of the performance standards are outlined below. Remove all noxious and undesirable weeds from the sit. Weeds shall include: Ragwort, Himalayan Balsam, Giant hogweed & Japanese knotweed, Thistle, Dock, Common Barberry, Male Wild Hop and Spring Wild Oat, or any other noxious species identified by the Department of Environment. For the removal of certain species such as Japanese Knotweed a method statement is to be prepared and submitted to the Department of Environment.

Performance Standards and Maintenance Operations

2.1 Grassed Areas

2.1.1 Fine-Cut Grass Areas

Fine cut grass areas shall achieve an even cover of vegetation of uniform height and colour comprising predominantly of grass species. No more than 5% of the grass areas shall contain dicotyledonous (dicots) weeds, except clover. Grass cutting shall not be carried out during excessively wet or waterlogged conditions. Contractor to inform administrative authority if conditions are unsuitable.

Fine-Cut Mowing

Where practical fine grass areas shall be cut using a cylinder mower, otherwise a rotary mower shall be used. All grass clippings shall be collected and removed off-site after each cut.

Lawn grass cutting shall be carried out every 10-14 days during the growing season, (throughout the period of March to October), but will need to be adjusted according to season's weather conditions. Grass shall be kept at a maximum height of 50mm and minimum height of 35mm. A minimum of 24 cuts shall be carried out annually.

Weed Control

Lawn grass areas shall be treated using an approved selective Glyphosate-free herbicide according to a registered professional user and manufacturer's instructions. Areas of invasive and noxious species in the lawn or areas, shall be mechanically removed or spot sprayed by a registered professional user.

Fertilizer

Approved fertilizer shall be applied 2no. times per year to lawn areas if required due to poor grass growth / establishment or yellowing. Spring fertilizer application of NPK ratio 9:7:7 shall be applied in May of each year and Autumn/Winter fertiliser of NPK ratio 3:12:12 shall be applied in October of each year to all fine cut grass areas.

2.1.2 Amenity Grass Areas

Amenity grass areas shall achieve an even cover of vegetation of uniform height and colour comprising predominantly of grass species. Unless otherwise agreed with the landscape architect no more than 15% of the grass areas shall contain dicotyledonous (dicots) weeds, except clover. Grass cutting shall not be carried out during excessively wet or waterlogged conditions. Contractor to inform administrative authority if conditions are unsuitable.

Amenity Grass Mowing

Where practical grass areas shall be cut using a cylinder mower, otherwise a rotary mower shall be used. Unless excessive or unsightly, or likely to cause a nuisance or damage to the sward, arisings shall be spread evenly over sward areas collected.

Lawn grass cutting shall be carried out every 10-14 days during the growing season, (throughout the period of March to October), but will need to be adjusted according to season's weather conditions. Grass shall be kept at a maximum height of 75mm and minimum height of 35mm. A minimum of 24 cuts shall be carried out annually.

Weed Control

Areas of invasive and noxious species in lawns, shall be mechanically removed. Glyphosate and other chemical pesticides will not be used under any circumstances unless otherwise instructed by a registered professional user. Weed infestations shall be reviewed in the context of the aesthetic and amenity functioning of the grass and if necessary controlled or eradicated.

Fertilizer

Approved fertilizer shall be applied 2no. times per year to lawn areas if required due to poor grass growth / establishment or yellowing. Spring fertilizer application of NPK ratio 9:7:7 shall be applied in May of each year and Autumn/Winter fertiliser of NPK ratio 3:12:12 shall be applied in October of each year to all fine cut grass areas.

2.1.4 Edging and Strimming

Grass edges along pathways, planting borders, roadways, trees, lampposts, signs and any other obstacle shall be kept neat and tidy at all times.

Between the months of March and October inclusive edging shall be carried out to all areas of grass abutting isolated/ specimen trees or shrub borders or mulch circles. These areas shall be maintained using a half moon tool or similar to maintain straight or curved defined line and shall be carried out a minimum of 2 - 3 times per year.

Mowing strips against permanent obstacles shall be a max. width of 150mm and shall be maintained using a hand strimmer. Large areas of desiccated/ burnt off grass are not permitted. Strimming shall be carried out a min. of 12 times per year.

Grass clipping and all arisings shall be swept up and removed off site.

2.1.5 Spring Bulbs in Grassed Areas

Only cut grassed areas populated by spring bulbs after the leaves of the bulbs have died down and/or yellowed completely. Initially reduce height by one third, followed by a 2-3 stage further reduction over two weeks to achieve desired grass height.

2.1.6 Failed areas

Areas of grass which fail or are damaged or worn shall be reinstated by re-turfing or re-seeding in accordance with the original specification.

2.2 Shrub Planting

Shrub areas shall be kept litter and weed free, particularly of perennial weeds. Healthy growth shall be maintained to cover as much as possible of the planting area and allowing the individual plants to achieve as near as possible their natural form. With the exception of hedges, boxing or pruning to shapes is prohibited. Plants shall be contained with designed planting areas and pruned to avoid obstructing pathways or sightlines. Climbers are to be pruned and tied into trellises as required, with two main inspections annually to check trellis system is intact and anchor points are secure.

2.3 Pruning

In general pruning shall be done only to enhance natural growth. Dead, damaged and diseased portions of the plant will be removed. All cuts shall be flush and clean, leaving no stubs or tearing of bark. All major pruning shall be done following flowering or during plant's dormant season. Emergency or minor pruning shall be done when needed.

Pruning shall be carried out to maintain proper size in relationship to adjacent plantings and intended function. Remedial attention and repair to shrubs shall be provided as appropriate by season or in response to incidental damage.

Groundcover plants shall be pruned as required to restrain perimeter growth to within planting bed areas where adjacent to walks and curbs. Tip prune selected branches of low growing shrub or groundcover masses to maintain even overall heights and promote fullness.

Certain plants, such as *Cornus* spp. will require heavy annual pruning in order to maintain healthy colourful stems and healthy leaves. All arising's from pruning shall be removed of site.

2.4 Weed Control

Planting beds shall be maintained relatively weed free (no more than 10% of weed cover at maximum) by hand weeding or spot spraying any emergent weeds during the growing season with Glyphosate-free herbicide or approved equivalent. Saplings shall be removed from all planting areas on emergence or immediately after to prevent establishment.

Specific weed control operations shall be carried out a min of 9no. times per year, however it will be the contractor's duty to control weeds by hand weeding or other accepted method if weed cover exceeds 10% of the planting area.

2.5 Mulching

Shrub beds shall contain a min. depth of 50mm bark mulch throughout the year. Contractor to top-up as 2 times per year or as appropriate to maintain depth. Mulch is not required in areas where plant foliage completely covers the soil surface, such that the soil is not visible through the foliage. The contractor shall spot treat to remove emergent weeds as specified above but do not cultivate or incorporate the mulch into the soil. Any mulch outside of designated planting areas shall be returned to the planter on a weekly basis.

Mulch shall be uniform in colour and appearance, and free of leaves, sticks, or trash. Mulch may be chipped or shredded wood, bark. When replacing existing mulch, use a mulch product that is similar in appearance to that already at the site.

2.6 Tree Planting Care

Trees shall be maintained in a healthy, vigorous growing condition with a well-shaped framework for future growth.

2.7 New Tree Planting

Spring and autumn of each year during the maintenance period the trees, double-stakes, rabbit guards and ties shall be checked and adjusted, the soil firmed, any dead wood removed back to healthy tissue and mulch adjusted to original levels. Any broken stakes or ties evident throughout the maintenance period shall be replaced.

A 1m-diameter mulch circle/square shall be maintained at the base of each tree located in open grass areas or grass verges. Top up bark mulch to 75mm where required and make good any mulch mats.

During the first growing season all standard trees / semi-mature trees shall be watered at least five times during the growing season - in April, May, June, July and August unless otherwise directed by the Landscape Architect. During the second growing season trees will be kept well watered, particularly during June, July and August.

The edge of the mulch circle shall be maintained in a neat and tidy condition as above.

The surface of all planting pits is to be kept free of weeds during the maintenance period by mechanical weeding of annual weeds and perennial weeds - to be carried out on three visits during the growing season.

2.9. Tree Stakes and Ties

Check tree stakes and ties on each maintenance visit. Repair, strengthen and adjust (loosen / tighten) to ensure optimum functioning and trees not being damaged by poor fixings. If trees no longer require stake / tie remove. Prior to handover, check all tree stakes and ties and remove those no longer required.

2.8 Woodland/Scrub Area Management

Woodland areas specified shall be maintained in a healthy, vigorous condition and free from litter and noxious weeds throughout the year.

Certain areas of woodland may require thinning over the 5-year period. These areas shall be thinned by no more than 10%, removing only the weaker tree specimens. Thinning shall be carried out as directed onsite by administrative authority.

Weed control around trees bases and in shrub areas will be achieved by mulches and mulch top ups only. Contractor to ensure that no damage is caused to trees by herbicide application.

Areas of natural scrub as indicated on the maintenance plans shall be contained by trimming back once per year. The contractor shall control noxious weeds. This shall be carried out 2no. times per annum.

All clearance operations within woodland and scrub areas shall be carried out outside of the bird-nesting season to preserve the bird life in the area. This season extends from the 1st March to 31st August.

2.10 Litter Clearance/Pick-up

The contractor shall maintain all areas free from litter. This shall mean the removal of all extraneous litter, rubbish and any other debris from all areas, which will include grass areas, planted areas, carparks, footpaths as well as woodlands and tree canopies.

Notwithstanding the above it is expected that the contractor and his staff shall take sufficient pride in the appearance of the site and that they would pick up all visible litter during every site visit.

In addition to removal of litter from footpaths, planted areas, etc., the contractor shall make provision for the immediate (within 1 days of notification) arrangement for collection and removal of all extraneous matter which has been deliberately been deposited on site by persons known or unknown (fly-tipping).

2.11 Replacements

Any tree, hedge or shrub that is removed, uprooted, destroyed or becomes seriously damaged, defective, diseased, or dead shall be replaced in the same location with another plant of the same species and size as that originally planted within the defect period after planting. All such replacements shall be carried out in the first available planting season after the requirement to do so is recognised.

3.0 Maintenance Programme

This programme is a guideline only and times of operations may vary on approval by landscape architect.

| ONGOING REQUIREMENTS: | JAN | FEB | MAR | APR | MAY | JUN | JUL | AUG | SEP | OCT | NOV | DEC |
|-----------------------------------------------------|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|
| Lawn grass cutting (Min 24 cuts) | * | ** | ** | ** | *** | *** | *** | *** | *** | ** | ** | |
| Edging to lawn grass areas | | | * | | | | * | | | * | | |
| Rough Grass | | | | | | | * | | | | | |
| Fertiliser application to lawn grass areas. | | | | | * | | * | | | * | | |
| Hedge pruning/cutting | | | | | * | | | * | | | * | |
| Shrubs pruning and feeding | | | * | | | * | | | * | | | |
| Weed control of hedge and shrub planting areas | * | * | * | * | * | * | * | * | * | * | * | * |
| Tree pruning | | | | | | | | | | * | * | |
| Removal of tree stakes (3-5yr) | | | | * | | | | | | | | |
| Mulch top-up to tree circles/ squares | | | | | | * | | | | * | | |
| Weed control to tree mulch circles | | | | * | | | * | | | | * | |
| Weed control to shrubs & hedgerow | | | * | | | | * | | | | * | |
| Watering of new trees (or after 3 weeks of no rain) | | | | * | * | * | * | * | | | | |
| Trimming of scrub areas | | | | | | | | | | | | * |
| Weed control of scrub areas | | | | * | | | | | * | | | |
| Weed control to footpaths, cycle paths. | | | | * | | | | | | | | |
| Litter Clearance/pick up | *** | *** | *** | *** | *** | *** | *** | *** | *** | *** | *** | *** |